

**ANSI & BS STANDARD WATER FLOW INDICTOR WITH RETARD****Type: ZSJZYS****Doc No: DS-901-ZSJZYS-01-E-X****1.0 PRODUCT OVERVIEW**

Flow indicator, usually installed in the system side of the pipe or pipe branch pipe, After a certain time delay (delay time 0-90s adjustable), when the water flow detected by the leaves, the water flow signal is converted into electrical signals, and electrical switch turn-on start-up Alarm system or directly start the fire pump and other electrical equipment, and can display the fire occurred area.

**Dimensions:**

2" (DN50)-10" (DN250)

**Design Standard:**

GB5135.7 UL 346 ULC-S548 FM1042

**Connection Standard:**

ISO 6182

**Working Pressure:**

2"~8" PN25/363PSI

10" PN16/300PSI

**Minimum Flow Rate For Alarm:**

4-10gmp (15-37.5L/min)

**Working Temperature:****Sign Off:**

Owner: \_\_\_\_\_ Contractor: \_\_\_\_\_ Engineer: \_\_\_\_\_  
Location: \_\_\_\_\_ Date: \_\_\_\_\_ Approved & Date: \_\_\_\_\_

0°C-68°C

## Electrical Ratings:

125/250VAC 5A 24/30VDC 3A

## Application:

Installation in the fire protection system, it and can indicate the fire occurred area.

## Surface Treatment:




- ☐ Epoxy power painting (color number as RAL3000, etc);
- ☐ Others' would be available upon clients' detailed request

## 2.0 APPROVALS



## 3.0 SPECIFICATIONS

### Product Sketch:



I

### Sign Off:

Owner: \_\_\_\_\_ Contractor: \_\_\_\_\_ Engineer: \_\_\_\_\_  
 Location: \_\_\_\_\_ Date: \_\_\_\_\_ Approved & Date: \_\_\_\_\_

| Part No. | Part                  | Standard Specification   | Options |
|----------|-----------------------|--------------------------|---------|
| 1        | Cover                 | ASTM B85-96 383.0E       |         |
| 2        | Body Gasket           | EPDM                     |         |
| 3        | Spring                | SS304                    |         |
| 4        | Air Delay Device      | PC GV3410R               |         |
| 5        | Stem Seal Assembly    | SS304+NBR                |         |
| 6        | Connecting Rod        | POM 500P                 |         |
| 7        | Switch Assembly       | PC GV3410R               |         |
| 8        | Connection Plate      | ASTM B85-96 383.0E       |         |
| 9        | Connection Plate Seal | EPDM                     |         |
| 10       | Body                  | ASTM A536,65-45-12       |         |
| 11       | Vane Assembly         | PE                       |         |
| 12       | U-Bolts               | Carbon Steel Zinc Plated | SS304   |
| 13       | Nuts                  | Carbon Steel Zinc Plated | SS304   |

## 4.0 DIMENSIONS AND PERFORMANCE

### 4.1 Dimensions

| Size  |     | Dimensio (mm) |       |     |       |     |      |                     | Certificate |
|-------|-----|---------------|-------|-----|-------|-----|------|---------------------|-------------|
| Inch  | mm  | R             | A±1.5 | B   | C±1.5 | D   | E±3  | HoleDia<br>(+1.6,0) |             |
| 2     | 50  | 60.3          | 116   | 100 | 63    | 140 | 83.5 | 30                  | UL/FM       |
| 2 1/2 | 65  | 73            | 120   | 100 | 63    | 140 | 83.5 | 30                  | UL/FM       |
| 2 1/2 | 65  | 76.1          | 122   | 100 | 63    | 140 | 83.5 | 30                  | UL/FM       |
| 3     | 80  | 88.9          | 145   | 100 | 63    | 140 | 94   | 51                  | UL/FM       |
| 4     | 100 | 114.3         | 185   | 100 | 63    | 140 | 94.5 | 51                  | UL/FM       |
| 5     | 125 | 139.7         | 212   | 100 | 63    | 140 | 94.5 | 51                  | UL/FM       |
| 5     | 125 | 141.3         | 212   | 100 | 63    | 140 | 94.5 | 51                  | UL/FM       |
| 6     | 150 | 165.1         | 254   | 100 | 63    | 140 | 95   | 51                  | UL/FM       |
| 6     | 150 | 168.3         | 254   | 100 | 63    | 140 | 95   | 51                  | UL/FM       |
| 8     | 200 | 219.1         | 298   | 100 | 63    | 140 | 95   | 51                  | UL/FM       |
| 10    | 250 | 273           | 381   | 100 | 63    | 140 | 97.5 | 70                  | —           |

#### Sign Off:

Owner: \_\_\_\_\_ Contractor: \_\_\_\_\_ Engineer: \_\_\_\_\_  
 Location: \_\_\_\_\_ Date: \_\_\_\_\_ Approved & Date: \_\_\_\_\_